

# *The Automatic Control Design and Simulation of Reactor Control System in Small Modular Reactor*

*Nuclear Power Institute of China*

*January, 2014*



- 1. Introduction*
- 2. The Small Modular Reactor (SMR) System Description*
- 3. The Automatic Control Design of the Reactor Power Control System (RPC) and the Steam Generator Feed Water Control System (FWC)*
- 4. Simulation Study*
- 5. Conclusion*




## ***1.1 The status of the SMRs in the world***

- ◆ ***The demands and applications of Nuclear Power Plant (NPP) are not only concentrated at the electricity generation but also some large-scale and enormous power consumption non-electricity applications.***
- ◆ ***More and more countries are developing the advanced Small Modular Reactor to meet the more extensive and diverse demands.***
- ◆ ***13 SMRs are under construction in six countries and the approximately 45 innovative SMR concepts research for electricity generation and other applications is being carried out.***



## 1.2 The demands for the SMRs in China

- ◆ In electricity generation domain
- ◆ In city heat supply domain
- ◆ In industrial and process heat supply domain
- ◆ In seawater desalination domain




- 1. Introduction*
- 2. The Small Modular Reactor (SMR) System  
Description*
- 3. The Automatic Control Design of the RPC and FWC*
- 4. Simulation Study*
- 5. Conclusion*



## 2.1 What does the SMR in China look like?

*It is an innovative PWR based on existing PWR technology, adapting “integrated” and “modular” reactor design technology.*



- ◆ Integrated head package
- ◆ eliminate the primary pipeline
- ◆ integrate the One-Through Steam Generator (OTSG) into the RPV

➔ *influence the characteristic of the control process of the reactor power and steam generator feed water flow*

↓  
*the automatic control design of the RPC and FWC is mostly affected by this integrated layout and the OTSG*



## *2.2 Main configuration of the SMR*

- ◆ forced circulation by 4 coolant pumps
- ◆ much shorter length of the coolant loops
- ◆ 4 groups of OTSG produces superheated steam
- ◆ few water inventory and the thermal-hydraulic process is rather adverse and rapid



## 2.3 The general control scheme

*The general control scheme for NSSS of the SMR*

- ◆ automatic control combined with the manual control
- ◆ The whole reactor control systems have an automatic control range from 0 to 100% full power (FP)
- ◆ the RPC and FWC use the manual scheme instead of automatic scheme below 20%FP
- ◆ automatic control within  $\pm 10\%$ FP step variations of the load and  $\pm 5\%$ FP/min ramp variations of the load

*The primary control principle is to maintain the main steam pressure at a constant and the reactor coolant average temperature at a constant*






- 1. Introduction*
- 2. The Small Modular Reactor (SMR) System Description*
- 3. The Automatic Control Design of the RPC and FWC***
- 4. Simulation Study*
- 5. Conclusion*




## 3.1 The automatic control scheme of the RPC

- ◆ The temperature control channel and the power mismatch control channel
- ◆ Introduce the feed water flow of the secondary side as the load signal




## 3.2 The automatic control scheme of the FWC (the feed water valve control scheme)

- ◆ The steam pressure control channel and the flow mismatch control channel
- ◆ Fast follow the mass demand of steam flow
- ◆ Delicately regulate the steam pressure with a PI controller



## 3.3 The automatic control scheme of the FWC (the feed water pump control scheme)

- ◆ Keep a linear mapping relation between the feed water flow and the FWV opening position
- ◆ Act fast enough to change the feed water heading and lead the feed water flow change




- 1. Introduction*
- 2. The Small Modular Reactor (SMR) System  
Description*
- 3. The Automatic Control Design of the RPC and FWC*
- 4. Simulation Study**
- 5. Conclusion*



## 4.1 The test bench and modeling

- ◆ The control process model is built in RELAP5
- ◆ The control system model is built in Simulink
- ◆ Data exchange via SQL Database
- ◆ Synchronized by Control Station



## 4.1 The test bench and modeling




### ◆ The model includes:

- Reactor
- 4 Integrated OTSG groups
- 4 Coolant pumps
- Feed water and steam pipelines
- 2 Feed water pumps
- Feed water and steam boundaries



## 4.2 The key factors of modeling for control simulation


- ◆ The reactor core is densely nodalized in order to calculate the temperature of the moderator fluid more precisely in the simulation
- ◆ The OTSG also needs a dense nodalization in order to catch the possible two-phase phenomenon in every node by using the correct flow regime and heat transfer formula in the simulation






## 4.3 Specified transient simulation

- ◆ The large-scale ramp load change within 20%FP and 100%FP



## 4.3 Specified transient simulation

### ◆ The step load change within 90%FP and 100%FP



- *The automatic control schemes are tested to be feasible within the simulation including large-scale ramp and step load change specified*
- *The reactor power control is related to the feed water control through the feed water flow considered as the load signal*
- *The control performance of both the primary and secondary loop is sensitive and closely coupled due to the transient of the integrated OTSG*



*Thanks for  
your attention!*

